

ADDENDUM



DATE: June 26, 2024 **ADD. NO.:** 2

PROJECT: Grizzly Flats Community Services District
CLEARWELL REPLACEMENT PROJECT

FROM: Scott Myers, Water Engineer

TO: All Bidders

PAGES: 2

The following addresses said Project specifications, plans, and agreement dated May 17th, 2024. Bidders must acknowledge receipt of this Addendum when submitting the Proposal. Failure to do so may subject the bidder to disqualification.

A. General

- **The project Bid Date remains unchanged, July 9th, 2024, at 2:00 p.m.**
- **The project engineering cost estimate is \$895,000.**
- **Earthwork Quantities: Cut – 376 CY; Fill – 130 CY (compacted)**
 - Contractor may leave surplus spoil on-site near the work area, as approved by Engineer. Contractor to clean spoil area of vegetation in advance. Provide erosion control wattles around spoil site before leaving the site.

B. Plans

1. See attached plan sheet C-4 for the following changes or clarifications:

- a. **Remove:** Replacement of existing 10" storm drain pipe with 12" pipe. Existing 10" storm drain shall remain in place as shown.
- b. **Add:** 12" butterfly valve on new tee connecting existing clearwell tank piping.
- c. **Replace:** 6" 90 ell with 6" tee at backwash pipe cut-in near existing pump station wood building.
- d. **Clarification:** 6" tank inlet pipe shall be ductile iron from point of connection to steel riser. A non-traffic rated lid for altitude valve vault is acceptable.
- e. **Clarification:** Install new 10" storm drain and inlet at slope and elevations, as shown.

Interested bidders can contact Cort Abney at (916) 806-3970, or cort@h2oengr.com for more information.

End of Addendum

